CSM\_E3S\_DS\_E\_7\_1

## **General-purpose Photoelectric** Sensor for High Quality and Reliable **Detection**





Be sure to read *Safety Precautions* on page 8.

## **Ordering Information**

#### **General-purpose Sensors**

Sensing method	Appearance	Sensing distance	Operation mode	Model
Through-beam *1		2 m		E3S-2E4 Emitter E3S-2LE4 Receiver E3S-2DE4
modgii bodiii i		5 m		E3S-5E4 Emitter E3S-5LE4 Receiver E3S-5DE4
Retro-reflective	C)	0.1 to 2 m		E3S-R2E4
Diffuse-reflective		100 mm		E3S-DS10E4
2		300 mm		E3S-DS30E4
		2 m	Light-ON/Dark-ON (selectable)	E3S-2E41 Emitter E3S-2LE41 Receiver E3S-2DE41
Through-beam *1		5 m		E3S-5E41 (42) *2 Emitter E3S-5LE41 (42) Receiver E3S-5DE41 (42)
Retro-reflective	Ų	0.1 to 2 m		E3S-R2E41
Diffuse-reflective		100 mm	E3S-DS10E41 E3S-DS30E41 (42) *2	E3S-DS10E41
2		300 mm		E3S-DS30E41 (42) *2
Convergent-reflective (narrow vision field)		30 to 100 mm (variable)		E3S-LS10XE4
Convergent-reflective (wide vision field)		50 to 250 mm (variable)		E3S-LS20XE4

Note: Sensors with open collectors and different frequencies are available.

<sup>\*1.</sup> Through-beam Sensors are normally sold in sets that include both the Emitter and Receiver.

Orders for individual Emitters and Receivers are accepted.

\*2. The difference between the E3S-□ (□□□) 41 and E3S-□ (□□□) 42 is in the lens direction when the Sensor is mounted. For details, refer to the dimensions that are provided on page 10 for the E3S-5E41, page 11 for the E3S-DS30E41, and page 12 for the E3S-5E42 and E3S-DS30E42.

## **Ratings and Specifications**


Sensing	g method	Through-beam		Retro-re- flective	Diffuse-reflective			Converger	nt-reflective
Item	Model	E3S-2E4 E3S-2E41	E3S-5E4 E3S-5E41 (42)	E3S-R2E4 E3S- R2E41	E3S- DS10E4 E3S- DS10E41	E3S- DS30E41 (42)	E3S- DS30E4S	E3S- LS10XE4	E3S- LS20XE4
Sensing o	listance	2 m	5 m	0.1 to 2 m	100 mm (white paper 50 x 50 mm)	300 mm (white paper	100 x 100)	30 to 100 mm Continuously variable (10 x 10 mm)	50 to 250 mm Continuously variable (50 x 75 mm)
Standard object	sensing	Opaque: 7- Opaque: 11- Opaque: 30- mm dia. min. mm dia. min.			Transparent, opaque				
Differentia	al travel				20% max. of setting distance			0.5 mm max. at 30 mm 3 mm max. at 100 mm	5% max. at 50 to 250 mm
Directiona	al angle	Both emitter a 3° to 10°	and receiver:	3° to 10°					l.
Light sou (waveleng		Infrared LED (950 nm)						RED LED (660 nm)	Infrared LED (950 nm)
Power su voltage	pply	12 to 24 VDC	12 to 24 VDC ±10%, ripple (p-p): 10% max.						
Current	tion	50 mA max. (Emitter: 25 mA max., Receiver: 25 mA max.)  40 mA max.							
Control of (solid-state put)	•	Output current: 1.5 to 4 mA, Load current: 80 mA max. (residual voltage: 2 V max.) → Refer to page 4.							
Response	time	Operate or reset: 3 ms max. Operate or reset: 1 ms max.							
Sensitivity adjustmen		With an indicator							
Ambient illumination (Receiver		Incandescent lamp: 3,000 lx max. Sunlight: 10,000 lx max.							
Ambient temperatu	ıre	Operating: -25 to 55°C, Storage: -40 to 70°C (with no icing or condensation)							
Ambient h	numidity	Operating: 35% to 85%, Storage: 35% to 95% (with no condensation)							
Insulation resistance		20 MΩ min. a	20 MΩ min. at 500 VDC						
Dielectric	strength	1,000 VAC, 5	0/60 Hz for 1 n	nin					
Vibration resistance (destructi		10 to 55 Hz, 1.5-mm double amplitude for 2 hours each in X, Y, and Z directions							
Shock res (destructi		500 m/s² 3 times each in X, Y, and Z directions							
Degree of protection		IEC IP65 IEC IP67 IEC IP65 IEC IP67							
Connection method	on	Pre-wired cable (standard length: 2 m)							
Indicators	•	Light indicator (red), Stability indicator (green)							
	Case	Polybuty- lene tereph- thalate							
Material	Lens *	Polycarbonate							
	Mount- ing Bracket	Iron	•						

<sup>\*</sup>The ambient operating illumination is the illumination that changes the output ±20% at 200 lx. It is not the operational limit.


## **Engineering Data (Typical)**

#### **Parallel Operating Range**

#### E3S-2E4 (41)




## E3S-5E4 (41) (42)




#### **Operating Range**


#### E3S-DS10E4 (41)




### E3S-DS30E4 (41) (42)



### E3S-LS10XE4




#### E3S-LS20XE4




## Sensing Distance vs. Size of Sensing Object

#### E3S-DS30E4 (41) (42) E3S-DS10E4 (41)




#### E3S-LS20XE4




#### **Parallel Operating Range**

#### E3S-R2E4 (41) (42)




#### **Excess Gain vs. Set Distance**


#### E3S-LS10XE4



#### E3S-LS3RC4



#### **Load Residual Voltage Characteristics**



# I/O Circuit Diagrams


Model	Wire color	Item Power polarity	Opera- tion mode	Output circuit	Timing charts
	Brown	+	Light-ON	Stability indicator (green)  Photo-electric Pensor main circuit Load 2 *2	Incident light  No incident light Light Indicator ON (red) OFF Output Typesider ON
E3S	Blue	0 V	Light-ON	Z: Zener diode (Vz = 30 V)  *1: Reverse the polarity of the power supply to switch the operating mode.  *2: Voltage output (when connecting transistor circuit)	transistor  Load 1  (e.g., relay)  Operate  Reset (Between brown and black)  Load 2  H  L (Between blue and black)
E33	Brown	0 V	Dark-ON	Light indicator (green)  Photo-electric electric rount circuit  Photo-electric rount circuit  Load 2 *2  Black  Load 1 (relay)	Incident light  No incident light Light Light ON (red) OFF Output Transistor ON
	Blue	+	Bank Giv	Blue *1 12 to 24 VDC  Z: Zener diode (Vz = 30 V)  *1: Reverse the polarity of the power supply to switch the operating mode. *2: Voltage output (when connecting transistor circuit)	Load 1 OFF (e.g., relay) Operate Reset (Between blue and black) Load 2 H L (Between brown and black)

### Connection

#### With Relay Load

#### **Through-beam Sensors**


Light Interrupted and Load Operating for E3S-2E4 (41) and -5E4 (41) (42)



Note: The indicator will function as a light indication if the Emitter's pink wire is connected to the Receiver's black wire as indicated by the dotted line. The indicator will function as a power indicator if the Emitter's pink wire is connected to the Emitter's blue wire.


#### **Retro-reflective Sensors**

Light Interrupted and Load Operating for E3S-R2E4 (41) (42), -DS10E4(41), and -DS30E4 (41) (42)




#### Connection with S3D2 Sensor Controller

Reverse operation is possible using the signal input switch on the S3D2.



## **Adjustment Methods**

#### Adjusting the E3S-LS10XE4 Convergent-reflective Sensor




- 1. Attach the distance adjustment scale as shown in the figure and set it where the \* mark is equal to the sensing distance.
- 2. Turn the distance adjuster until the red spot is at point (a (center of the distance adjustment scale).
- 3. Remove the distance adjustment scale once the distance has been adjusted. Put a sensing object in place, and then adjust the sensitivity.

#### Adjusting the E3S-LS20XE4 Convergent-reflective Sensor

#### **Adjustment Method 1**


Use this method if the sensing object is more reflective than the background.



- Set the sensitivity adjuster to the center as shown in the figure.
- Turn the distance adjuster counterclockwise until it is fully turned (L to S).
- 3. Position the sensing object.
- 4. Slowly turn the distance adjuster clockwise (S to L).
- 5. Eventually the LIGHT (red) indicator will light. Turning the adjuster further will <u>light the STABILITY (green) indicator</u>. <u>Leave the distance adjuster at this level</u>.
- Adjust the sensitivity in this state.

#### **Adjustment Method 2**

Use this method if the background is more reflective than the sensing object.



- 1. Set the sensitivity adjuster to the center as shown in the figure.
- 2. Turn the distance adjuster clockwise until it is fully turned (S to L).
- 3. Remove the sensing object.
- 4. Slowly turn the distance adjuster counterclockwise (L to S).
- 5. Eventually the LIGHT (red) indicator will light. Turning the adjuster further will <u>light the STABILITY (green) indicator</u>.
- 6. Adjust the sensitivity in this state.

## **Safety Precautions**

## **MARNING**

This product is not designed or rated for ensuring safety of persons.


Do not use it for such purposes.



#### **Precautions for Correct Use**


Do not use the product in atmospheres or environments that exceed product ratings.

If the sensing object has a metallic or shiny surface, the E3S-R may not detect it properly. To avoid this situation, place the sensing object so that it is not at right angles to the Photoelectric Sensor.



#### Attaching the E39-S Slit

- The Slit can be fitted vertically or horizontally as indicated by the dotted line. Make sure that Slits for the Emitter and the Receiver are fitted in the same orientation.
- Place the packing in the supporter and hook the claws on the indentations in the Sensor head.
- If the supporter is contacting the mounting surface, insert a spacer to separate it. (Refer to *Slit Dimensions*.)
- An operating position accuracy of 0.1 mm max. can be achieved for a Through-beam Sensor without Slits.



#### **Sensor with Slits**

Applicable Photoelectric Sensor		E3S-5E4	, -5E41 (42)	E3S-2E4, -2E41			
Model		E3	9-S1		E39-S2		
Item Slit width	0.5 mm 1 mm 2 mm 4 mm			0.5 mm	1 mm	2 mm	
Sensing distance	230 mm	580 mm	1200 mm	2500 mm	170 mm	420 mm	820 mm
Sensing object	0.5 mm	1 mm	2 mm	4 mm	0.5 mm	1 mm	2 mm
Degree of protection	IP60						

#### Sensors with Open-collector Outputs

#### **Sensors with Open-collector Outputs**


Туре	Output type	Output transistor	Rated current output	Switching current	Output protection circuit
E	Voltage or current output	NPN	1.5 to 4 mA	80 mA max. (sinking)	Provided against an increase in the residual output voltage
С	Open- collector output	NPN		100 mA max. (sinking)	Provided: Output transistor cutoff
В	Open- collector output	PNP	ı	100 mA max. (sourcing)	Provided: Output transistor cutoff

The model numbers are as follows:


Example:

E3S-DS10E4 (E type) E3S-DS1C4 (C type) E3S-DS1B4 (B type)

#### C4 (C41, C42) Sensors



#### C4 (B41, B42) Sensors



Z: Zener diode (Vz = 30 V)

\* The operation mode depends on the wiring of the brown and blue lines.

Note 1. Only C42 models with die-cast cases are available.

- 2. The Emitter for a Through-beam C4-type Sensor is the same as the Emitter for an E4-type Sensor. (E.g., E3S-5LE4)
- When a C- or B- type Sensor experiences a load short-circuit or overload, the output transistor will be turned OFF. Check the load conditions before turning the power back ON.

### Sensors with Different Orientations


The E3S-5, E3S-DS30, and E3S-R2 that sense in different directions can be made.

Sensing method	Sensing direction
Through- beam	E3S-5E43  E3S-5E44  Emitter  Receiver  Receiver
Retro- reflective Diffuse- reflective	E3S-DS30E43 E3S-R2E43


#### **Dimensions**

#### **General-purpose Sensors**


#### E3S-2E4 4-dia, vinvl-insulated round cable with 2/3 conductors (Conductor cross section: 0.2 mm², Insulator diameter: 1.1 mm), Standard length: 2 m Weight: Emitter and Receiver, 80 g each Sensitivity adjuster\*2 Indicato (50) <del>-</del>-18.8 40 |<del>-</del>9<del>-</del>|-11. 6 dia. Lens: 7 dia 12.8 dia. 3.2 E39-L3 -9--20 **-**16 2-Two, M3 -25.1 $^{*1}$ The mounting bracket can also be used on side (A). $^{*2}$ Receiver only.



#### E3S-5E4



#### E3S-5E41




Note: Models numbers for Through-beam Sensors (E3S-□E4, E3S-□E41) are for sets that include both the Emitter and Receiver.

The model number of the Emitter is expressed by adding "L" to the set model number (example: E3S-2LE4), the model number of the Receiver, by adding "D" (example: E3S-2DE4.) Refer to Ordering Information to confirm model numbers for Emitter and Receivers.

#### E3S-DS10E4



4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.2 mm², Insulator diameter: 1.1 mm), Standard length: 2 m Weight: Approx. 80 g




\* The mounting bracket can also be used on side (A).

#### E3S-DS10E41




4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.2 mm², Insulator diameter: 1.1 mm), Standard length: 2 m Weight: Approx. 80 g



#### E3S-R2E4 E3S-DS30E4




4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.2 mm $^2$ , Insulator diameter: 1.1 mm), Standard length: 2 m Weight: Approx. 155 g



#### E3S-R2E41 E3S-DS30E41





4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.2 mm², Insulator diameter: 1.1 mm), Standard length: 2 m Weight: Approx. 165 g



\* The mounting bracket can also be used on side (A).

#### E3S-5E42





Note: Models numbers for Through-beam Sensors (E3S-5E42) are for sets that include both the Emitter and Receiver.

The model number of the Emitter is expressed by adding "L" to the set model number (example: E3S-5LE42), the model number of the Receiver, by adding "D" (example: E3S-5DE42.) Refer to Ordering Information to confirm model numbers for Emitter and Receivers.

#### **Mounting Hole Dimensions**


E3S-2E4 E3S-LS10XE4 Two, M3 E3S-5E4 E3S-DS30E4 Two, M4 E3S-DS10E4 E3S-DS10E4 E3S-DS10E4 E3S-DS10E4 E3S-R2E4 E3S-R2E4


## **Accessories (Order Separately)**


#### **Special Mounting Bracket**

#### E39-L2













Applicable models: E3S-5E41 E3S-R2E41 E3S-DS30E41

E39-L4










Reflector

E39-R1

(Provided with the E3S-R2E4(41) Retro-reflective Reflector.)






## Sensitivity Adjuster (Provided)

E39-G1







Applicable models: Provided with the E3S-5E4(41), E3S-DS30E4(41), E3S-R2E4(41). Note: Cannot be used for the E3S-DS10E4 (41).

### Slit (Order Separately)

E39-S2








Slit	E39-S2
Applicable	E3S-2E4
Sensors	E3S-2E41


Note 1. Three sets of slits are provided:  $6.5\,x\,0.5$  mm,  $6.5\,x\,1$  mm and  $6.5\,x$ 2 mm

One set consists of two slits, one each for the Emitter and Receiver.

E39-S1







Slit	E39-S1
Applicable	E3S-5E4
Sensors	E3S-5E41

Note 1. Four sets of slits are provided: 11 x 0.5 mm, 11 x 1 mm, 11 x 2 mm, and 11 x 4 mm 2. One set consists of two slits, one

each for the Emitter and Receiver.

Note: The dimensions in parentheses are for when the Spacer is not used.

\*With the E3S-2E4 (41), use the Spacer as shown in the figure above so that the supporter and Mounting Bracket will not be struck when the optical axis is adjusted.

With the E3S-5E4 (41), the Spacer is not particularly required. Use the Spacer, however, to directly mount both the E3S-2E4 (41) and -5E4 (41).

In the interest of product improvement, specifications are subject to change without notice.

#### Read and Understand This Catalog

Please read and understand this catalog before purchasing the products. Please consult your OMRON representative if you have any questions or comments.

#### Warranty and Limitations of Liability

#### WARRANTY

OMRON's exclusive warranty is that the products are free from defects in materials and workmanship for a period of one year (or other period if specified) from date of sale by OMRON.

OMRON MAKES NO WARRANTY OR REPRESENTATION, EXPRESS OR IMPLIED, REGARDING NON-INFRINGEMENT, MERCHANTABILITY, OR FITNESS FOR PARTICULAR PURPOSE OF THE PRODUCTS. ANY BUYER OR USER ACKNOWLEDGES THAT THE BUYER OR USER ALONE HAS DETERMINED THAT THE PRODUCTS WILL SUITABLY MEET THE REQUIREMENTS OF THEIR INTENDED USE. OMRON DISCLAIMS ALL OTHER WARRANTIES, EXPRESS OR IMPLIED.

#### LIMITATIONS OF LIABILITY

OMRON SHALL NOT BE RESPONSIBLE FOR SPECIAL, INDIRECT, OR CONSEQUENTIAL DAMAGES, LOSS OF PROFITS OR COMMERCIAL LOSS IN ANY WAY CONNECTED WITH THE PRODUCTS, WHETHER SUCH CLAIM IS BASED ON CONTRACT, WARRANTY, NEGLIGENCE, OR STRICT LIABILITY.

In no event shall the responsibility of OMRON for any act exceed the individual price of the product on which liability is asserted.

IN NO EVENT SHALL OMRON BE RESPONSIBLE FOR WARRANTY, REPAIR, OR OTHER CLAIMS REGARDING THE PRODUCTS UNLESS OMRON'S ANALYSIS CONFIRMS THAT THE PRODUCTS WERE PROPERLY HANDLED, STORED, INSTALLED, AND MAINTAINED AND NOT SUBJECT TO CONTAMINATION, ABUSE, MISUSE, OR INAPPROPRIATE MODIFICATION OR REPAIR.

#### **Application Considerations**

#### SUITABILITY FOR USE

OMRON shall not be responsible for conformity with any standards, codes, or regulations that apply to the combination of products in the customer's application or use of the products.

At the customer's request, OMRON will provide applicable third party certification documents identifying ratings and limitations of use that apply to the products. This information by itself is not sufficient for a complete determination of the suitability of the products in combination with the end product, machine, system, or other application or use.

The following are some examples of applications for which particular attention must be given. This is not intended to be an exhaustive list of all possible uses of the products, nor is it intended to imply that the uses listed may be suitable for the products:

- · Outdoor use, uses involving potential chemical contamination or electrical interference, or conditions or uses not described in this catalog.
- Nuclear energy control systems, combustion systems, railroad systems, aviation systems, medical equipment, amusement machines, vehicles, safety equipment, and installations subject to separate industry or government regulations.
- Systems, machines, and equipment that could present a risk to life or property.

Please know and observe all prohibitions of use applicable to the products.

NEVER USE THE PRODUCTS FOR AN APPLICATION INVOLVING SERIOUS RISK TO LIFE OR PROPERTY WITHOUT ENSURING THAT THE SYSTEM AS A WHOLE HAS BEEN DESIGNED TO ADDRESS THE RISKS, AND THAT THE OMRON PRODUCTS ARE PROPERLY RATED AND INSTALLED FOR THE INTENDED USE WITHIN THE OVERALL EQUIPMENT OR SYSTEM.

#### PROGRAMMABLE PRODUCTS

OMRON shall not be responsible for the user's programming of a programmable product, or any consequence thereof.

#### **Disclaimers**

#### **CHANGE IN SPECIFICATIONS**

Product specifications and accessories may be changed at any time based on improvements and other reasons.

It is our practice to change model numbers when published ratings or features are changed, or when significant construction changes are made. However, some specifications of the products may be changed without any notice. When in doubt, special model numbers may be assigned to fix or establish key specifications for your application on your request. Please consult with your OMRON representative at any time to confirm actual specifications of purchased products.

### **DIMENSIONS AND WEIGHTS**

Dimensions and weights are nominal and are not to be used for manufacturing purposes, even when tolerances are shown.

#### PERFORMANCE DATA

Performance data given in this catalog is provided as a guide for the user in determining suitability and does not constitute a warranty. It may represent the result of OMRON's test conditions, and the users must correlate it to actual application requirements. Actual performance is subject to the OMRON Warranty and Limitations of Liability.

#### **ERRORS AND OMISSIONS**

The information in this document has been carefully checked and is believed to be accurate; however, no responsibility is assumed for clerical, typographical, or proofreading errors, or omissions.

20<u>11.9</u>

In the interest of product improvement, specifications are subject to change without notice.



## **X-ON Electronics**

Largest Supplier of Electrical and Electronic Components

Click to view similar products for Photoelectric Sensors category:

Click to view products by Omron manufacturer:

Other Similar products are found below:

E3JM-DS70R4T-US E3L2DC4 E3RA-DN12 2M E3RA-DP12 2M E3S5LE4S E3S-AD38 E3S-CR11 5M E3SCT11D5M E3SCT11M1J03M E3T-CT22S E3T-FD12R E3T-SL14R E3T-SL24 5M E3T-ST12R E3T-ST24 2M E3X-CN02 E3X-CN11 5M E3X-CN21 10M E3ZM-B66 E3ZM-CL81H 2M E3Z-T62 2M NJL5303R-TE1 PB10CNT15PO PD60CNX20BP FZS CX-491-P-J CX-491-Z XUM2BKCNL2T E3T-SL21 5M E3T-SL21 5M E3T-SL21 5M E3T-SL11R E3T-ST12 5M E3X-DA41-S-M1J 0.3M E3X-DAB6 E3X-DAG8 E3ZM-B86