Flashers and Tower Lighting Controls

Tower and Obstruction Lighting Controls




SCR9L

Universal Lamp Alarm Relay




Wiring Diagram

BEACON LAMP CONNECTION DIAGRAM



OBSTRUCTION LAMP CONNECTION DIAGRAM



V = Voltage

- B = Beacon Lamps SS = Selector Switch
- L = LED Indicator
- F = Flasher
- AXL = Auxiliary
- Load/Alarm
- OL = Obstruction Lamps SI = Sensor Input
- H = "3" Spare AC Hot
 - Connection (2A max.)

Description

The SCR9L is a universal lamp alarm relay designed to sense the failure of flashing or steady LED beacon lamps or obstruction lamps. The SCR9L energizes when one or more lamps fail. It will monitor the operation of one to eight beacon or obstruction lamps. All monitored lamps must be the same wattage and voltage. When connected to a site monitoring system, it provides the remote lamp monitoring protection required by the FAA-AC No: 150/5345-43E.

Operation

When a lamp fails, the SCR9L senses a decrease in current flow. After a 10s trip delay, the onboard LED glows and the two alarm outputs energize. The outputs and the LED are reset when the failed lamps are replaced and the unit is recalibrated. The SCR9L will sense an open flasher, it will not sense a continuously ON flasher (see FB Series). Removing input voltage de-energizes the output and the LED's. It does not change the calibration.

Features & Benefits

FEATURES	BENEFITS
Self calibrating	Designed for use with all types of LED beacon and obstruction lamps
Failsafe beacon monitoring	Relay will also provide an alarm signal on a failed flasher (open)
Number of lamps monitored is switch selectable up to 8	User selection allows quick set up and easy adaption to multiple applications
Universal voltage 120 to 230VAC	Designed for use in most applications
Isolated, 10A, SPDT alarm output contacts	Provides remote beacon monitoring when connected to a site monitoring system, as is required by the FAA
LED indication	Provides visual relay status of operation, alarm, trip delay, and calibration
Fully encapsulated	Protects against shock, vibration, and humidity

Accessories



C103PM (AL) DIN Rail

35 mm aluminum DIN rail available in a 36 in. (91.4 cm) length.



P1023-20 DIN Rail Adapter Allows module to be mounted on a 35 mm DIN

type rail with two #10 screws.

Flashers and Tower Lighting Controls

Tower and Obstruction Lighting Controls



CE

Calibration

SCR9L

Alarm relays must be calibrated at initial installation and when LED lamps are replaced. Due to LED lamp aging, recalibration is recommended every 12 months.

- 1. Remove input voltage
- 2. Move calibration switch to off position
- 3. Re-apply input voltage
- 4. LED will flash red to indicate the unit is ready for calibration
- 5. Visually inspect structure's lighting to make sure all lamps and flashers (if used) are operating properly
- 6. Remove input voltage
- 7. Adjust lamp selector switches for the correct number of lamps to be monitored (see adjustment diagram below)
- 8 Re-apply input voltage
- 9. LED should flash red
- 10. Move calibrate switch to ON position
- 11. The LED will alternate flashing red and green
- 12. LED will glow steady green within 30 secs. Calibration is complete


Calibration Failed

If the LED double blinks red, calibration failed. Remove input voltage and repeat steps 6-8.

Notes:

- Monitoring a mixture of LED beacons and LED obstruction a. lamps is not possible with the SCR9L.
- This alarm relay is not designed to monitor b. incandescent lamps.
- c. Applying input voltage when the calibrate switch is in the OFF position, erases the previous calibration settings. The LED will flash Red. The output relays are OFF and the unit will not sense lamp failures.
- Only one temperature compensated LED beacon can d. be monitored with this product. A combination of temperature compensated and standard LED beacons cannot be monitored.

Adjustment Example



Example Shown: SCR9L two lamps are ON during normal operation.

Indicator Table

L	Green	Input ON & Calibrated
L	Green Flashing	Trip Delay
L	Red	Lamp Failure
L	Red/Green Flashing	Calibrating
L	Red Flashing	Not Calibrated

Specifications Sensors

Sensors	
Calibration Range	
(total all Lamps)	150mA - 8.0A
Absolute Max Current	
(total all Lamps)	15A max. (may not calibrate above 8A)
Single Lamp Current	150mA - 8.0A (total all lamps < 8.0A)
Time Delay	
Trip Delay	Factory fixed ≅10s
Input	
Input Voltage/Tolerance	120 to 230VAC ±15%
AC Line Frequency	50/60Hz
Output	To operate a spare lamp or alarm
Line Voltage Output (SPNO)	5A @ 240VAC or 30VDC resistive;
	1/4 hp @ 125VAC; 1/2 hp @ 250VAC
Isolated Alarm Output (SPDT)	10A @ 240VAC or 30VDC resistive;
-	1/4 hp @ 125VAC; 1/2 hp @ 250VAC
Auxilliary Input Voltage (H)	≤ 2A @ 230VAC
Mechanical	
Mounting	One #10 (M5 x 0.8) screw
Dimensions	H 76.7 mm (3"); W 51.3 mm (2.02");
	D 41.7 mm (1.64")
Termination	IP20 screw terminals for up to 14 AWG
	(2.45 mm²) wire or two 16 AWG
	(1.3 mm ²) wires
Protection	
Circuitry	Encapsulated
Environmental	-
Operating / Storage	
Temperature	-40° to 60°C / - 40° to 85°C
Weight	≃ 3.9 oz (111 g)

X-ON Electronics

Largest Supplier of Electrical and Electronic Components

Click to view similar products for Time Delay & Timing Relays category:

Click to view products by Littelfuse manufacturer:

Other Similar products are found below :

5NO30 614-11B-0A2 614-11B-OA3 614-11B-OA4 614-11B-OA6 614-11B-OA8 614-11C-OA1 614-11C-OA2 614-11C-OA5 614-11Q-OA3 614-11Q-OA6 614-11T-OA3 614-11T-OA6 614-11T-OA7 614-12B-4A1 614-12C-400 614-12Q-400 614-12T-600 614-22T-4A1 614-43B-400 614-43C-100 614-43F-200 614-43Q-0A2 614-43Q-100 614-43Q-600 614-43T-0A9 614-43T-600 614-43U-400 614-43U-4A1 614-43U-6A2 615-21T-200 655-11T-100 655-11U-500 655-12T-300 655-22T-400 655-22T-600 CUA-41-30001 CUA-41-30030 CUA-41-70180 CUA-41-71038 CUA-42-30005 CUA-42-30010 CUA-42-30120 CUA-42-70120 CUA-99-72502 CUC-41-30030 CUF-42-30010 CUH-41-31006 7012AFX 7012GD