
| I | PART NUMBER | SSI-LXR3612SOD-150 | REV. | Α |
|---|-------------|-------------------------------------|------|------|
| I | DATE | E.C.N. NUMBER AND REVISION COMMENTS | | REV. |
| | 05.24.16 | ECN-Lumex201600011 | | Α |



| ELECTRO-OPTICAL | CHARACTERISTICS | Ta=25°C |
|-----------------|-----------------|---------|
| | | |

| PARAMETER | MIN | TYP | MAX | UNITS | UNITS |
|--------------------|-----------------|-----|-----|------------|----------|
| PEAK WAVELENGTH | | 610 | | nm | |
| FORWARD VOLTAGE | | 2.1 | 2.5 | Vf | If=20mA |
| REVERSE VOLTAGE | | | 5.0 | Vr | Ir=100µA |
| LUMINOUS INTENSITY | | 100 | | mcd | If=20mA |
| VIEWING ANGLE | | 60 | | 2 theta1/2 | |
| EMITTED COLOR: | ORANGE | | | | |
| EPOXY LENS FINISH: | ORANGE DIFFUSED | | | | |

LIMITS OF SAFE OPERATION AT 25°C

| PARAMETER | MAX | UNITS |
|-----------------------|------------|-------|
| PEAK FORWARD CURRENT* | 150 | mA |
| FORWARD CURRENT | 30 | mA |
| POWER DISSIPATION | 105 | mW |
| DERATE FROM 25°C | -1.6 | mW/*C |
| OPERATING TEMP. | -40 TO +85 | °C |
| STORAGE TEMP. | -40 TO +85 | •c |
| * t<10µS | | |

NOTES:

- SSL-LX3054SOD, ORANGE LED, TRIM LEADS TO 5mm.
 SSI-LXR3612 HOLDER, CHROME FINISH.
 SSH-LXH1612BSG, BUSHING. INSERT AND CRIMP.
 ANODE LEAD: LXP-WST26R0TOC, 26 AWG. STRANDED, RED INSULATION, CUT TO 157mm LONG, STRIP ENDS 2mm AND 9.5mm.
- 5. CATHODE LEAD: LXP-WST26BLTOC, 26 AWG. STRANDED, BLACK INSULATION, CUT TO 157mm LONG, STRIP ENDS 2mm AND 9.5mm.
- 6. SOLDER LED LEADS TO WIRE LEADS.

*UNLESS OTHERWISE SPECIFIED TOLERANCES PER DECIMAL PRECISION ARE: X=±1 (±0.039), X.X=±0.5 (±0.020), X.XX=±0.25 (±0.010), X.XXX=±0.127 (±0.005). LEAD SIZE=±0.05 (±0.002), LEAD LENGTH=±0.75 (±0.030). MIN= +DECIMAL PRECISION MAX.= +0.00 (±0.002), X.XX=±0.127 (±0.005).



425 N. GARY AVE. CAROL STREAM, IL 60188 PHONE: 800-278-5666 FAX: 630-315-2150

WEB: WWW.LUMEX.COM

T-3mm (T-1) 610nm AlinGaP ORANGE LED PANEL INDICATOR, ORANGE DIFFUSED LENS, WITH 6" WIRE LEADS.

THE SPECIFICATIONS MAY CHANGE AT ANY TIME WITHOUT NOTICE DUE TO NEW MATERIALS OR PRODUCT IMPROVEMENT.

CONFIDENTIAL INFORMATION CONTAINED IN THIS DOCUMENT IS THE PROPERTY OF LUMEX INC. SPECIFICALLY AUTHORIZED IN WRITING BY LUMEX INC., THE HOLDER OF THIS DOCUMENT SHALL KEEP ALL INFORMATION CONTAINED HEREIN CONFIDENTIAL AND SHALL PROTECT SAME IN WHOLE OR IN PART FROM DISCLOSURE AND DESEMBATION TO ALL THIRD PARTIES.

DATE: 05.24.16 DRAWN BY: E.C. PAGE: 1 OF 1 CHKD BY: G.Y. SCALE: NTS APRVD BY: Ray **P** UNIT: mm [INCH]

X-ON Electronics

Largest Supplier of Electrical and Electronic Components

Click to view similar products for LED Panel Mount Indicators category:

Click to view products by Lumex manufacturer:

Other Similar products are found below:

607-3232-140F 821-0331-503 FL2870C8R FL2950WL7B FL2950WL8G FL589WL8R FL67C8R H8630FBBA3 NL177WL2A NL177WL3G NL276C2A NL2950BWL3G NL589WL2R NL67C2C NL67C3R C480AABG3 PB22BM41K PB22SIM40Y PB22SKRS31KC L32R-R2-2311 L3353-MWRG L39UR-R24-2111 L58D-G2-W L58D-Y2-W L59D-R12-W L59UD-R12-W L625DG L625DR LE177WL39007 LE2950BWL39018 LH1048BSWL3702 LH1048BWL3702 LH382A LH677G LHM628A FL276WL7R FL2950BWL7R FL2950WL8R FL2950WL8R-12 FL2951WL8G FL2951WL8R FL589C7R FL67WL8G MPC5BCW18.0 556-1605-808F 556-1705-809F 556-3008-839F 558-0201-818F 559-0001-813F